

VDH-LP SWAP

Low Income Qualified Residential Septic Repair/Replacement, Well Replacement, Abandonments, Sewer Connections, and Public Water Connections

Contractors:

The Middle Peninsula Planning District Commission Septic and Well Assistance Program is soliciting bids for the attached project. Projects are supported by a grant program funded by the Virginia Department Health (VDH) and administered by the Middle Peninsula Planning District Commission (MPPDC) Septic and Well Assistance Program.

Grant funds will be utilized to fund 100% of the approved amount. The attached project has already been qualified for grant funding and the next phase is to solicit bids from contractors.

Attached you will find an itemized bid sheet breaking out certain costs and acknowledgments that need to be captured, a scope of work, and existing permits. Awarded projects are to be completed in a timely manner. All work must be completed before the expiration of permits. Work is done for the MPPDC SWAP Program, who disperses payment. You will receive a Notice to Proceed if you are awarded the project.

The grant has a hard deadline, to be reimbursed by this program all work, associated paperwork, invoices, and receipts must be dated prior to and received by the MPPDC SWAP Program Manager no later than June 30th, 2025.

For additional information or assistance, please contact Taylor Ovide, Coastal Resilience Planner at (804) 758-2311 or tovide@mppdc.com.

COMMISSIONERS

Essex County Hon. Edwin E. Smith, Jr. Hon. John C. Magruder Ms. Sarah Pope

Town of Tappahannock Hon. Katherine B. Carlton

Gloucester County

Hon. Ashley C. Chriscoe (Chairman) Hon. Michael W. Hedrick Dr. William G. Reay

King and Queen County

Hon. Sherrin C. Alsop Hon. R. F. Bailey Ms. Vivian Seay

King William County

Hon. Edwin H. Moren, Jr. Hon. Travis J. Moskalski (Vice-Chairman) Mr. Otto O. Williams Mr. Percy C. Ashcraft

Town of West Point

Hon. James M. Pruett Mr. John B. Edwards, Jr.

Mathews County

Hon. Melissa Mason Hon. David Jones Mr. Harry Meeks Ms. Ramona Wilson

Middlesex County Hon. Wayne H. Jessie, Sr. (Treasurer) Hon. Reggie Williams, Sr. Ms. Kendall Webre

Town of Urbanna Hon. Dr. William T. Goldsmith

Secretary/Director Mr. Lewis L. Lawrence, III

> Saluda Professional Center * 125 Bowden Street * P.O. Box 286 * Saluda, Virginia 23149 (Phone) 804 758-2311 * (Fax) 804 758-3221 * (Email) pdcinfo@mppdc.com https://www.mppdc.com

Onsite Sewage System Evaluation and Desing Project (2023-MPPDC-06S) Address: 345 Airport Rd, Mattaponi, VA 23110

Cost for Line Item #1 (include total cost for items A-L) These are known factors. Vendors must invoice for actual cost incurred as described in the attached scope of work and permits.

Total					
	Line 1 Total Bid Cost				
Line Item # 1 ; The contractor shall furnish all labor, supervision, equipment, tools, parts, supplies and materials, as necessary, to perform the services as described in the scope of work:	\$				
Itemized Include	ed in Line 1:				
	Itemized Bid Cost				
A) Conduct onsite sewage system site evaluations and submit onsite sewage system designs pursuant to all applicable laws and regulations:	\$				
B) Costs of Septic Pump-out by a licensed sewage hauler to appropriatly evaluate the system (prior to all site and soil evaluations):	\$				
C) Provide or subcontract with a licensed Surveyor and mark the boundries for all subject properties(this is only required if you find the attached survey inadequate):	\$				
D) Obtain an onsite sewage system repair permit for each of the subject properties from the applicable local health department (no LHD fee for the repair permit):					
Additional Itemized Costs <u>N</u>	NOT Included In Line 1:				
Additional costs not included in line item 1:	\$				

Signature: _____

_ Date __

Bid is good for _____days

The following are required. Please initial in agreement to perform the following and that any costs to

perform these tasks are included in Line Item 1:			
	Initial on the lines below;		
I) Bidders shall comply with all requirements of DPOR for contracting and executing the contract with the MPPDC.			
Must submit invoice to tovide@mppdc.com once Local Health Department has issued the Repair Permit.:			

Project #: 2023-MPPDC-06S Project Title: SWAP LP Scope of Work – Onsite Sewage System Evaluation and Designs

The contractor shall furnish all labor, supervision, equipment, tools, parts, supplies and materials, as necessary, to perform the services as described herein:

A) Conduct onsite sewage system site evaluations and submit onsite sewage system designs pursuant to the Sewage Handling and Disposal Regulations (12VAC5-610-10 et. seq., the Regulations) and the Regulations for Alternative Onsite Sewage Systems (12VAC5-613-10 et. seq., the AOSS Regulations), and all other applicable state and local laws, regulations and ordinances for repair of existing onsite sewage systems. Site evaluations and design shall be submitted to the applicable local health department for the following properties:

• 345 Airport Rd, Mattaponi, VA 23110 (2023-MPPDC-06S)

Site evaluations and designs shall include property marking of all utilities, and review of all relevant records for neighboring parcels. Designs shall fully comply with the Regulations and AOSS Regulations; designs cannot rely upon the issuance of treatment or pressure dosing waivers for permitting.

B) Prior to all site and soil evaluations, the contractor shall have the contents of the existing septic tank serving the subject properties pumped by a properly licensed sewer hauler to allow for a complete malfunction assessment.

C) Provide or subcontract with a licensed surveyor to survey and mark the boundaries for all subject properties. Partial property boundary surveys of only the boundary closest to the proposed repair site are allowable for properties greater than 3 acres in size.

D) Obtain an onsite sewage system repair permit for each of the subject properties from the applicable local health department. Please note that all homeowners have already been determined to be fiscally eligible for a permit fee waiver so there will not be a cost associated with acquiring the repair permit.

E) Comply with all requirements of the Department of Professional and Occupational Regulations (DPOR) for contracting and executing the contract with the Virginia Department of Health. Must provide a copy of a Master Alternative Onsite Soil Evaluator license from DPOR.

Optional site visit: Available upon request.

<u>Notes:</u> A past survey, photo, and LHD documentation are attached. Site visit is encouraged as the site is compact with some potential design challanges. The LHD notes in their Construction Permit denial "Insufficient depth of suitable soil to seasonal water table.", and "Insufficient area of acceptable soil for a conventional drainfield." "Contact Private Sector to design proposed repair."

Additional questions:

Contact Taylor Ovide via email: tovide@mppdc.com or phone at 804-758-2311



THREE RIVERS HEALTH DISTRICT P.O. BOX 415 SALUDA, VIRGINIA 23149

June 27, 2023

Gloria Chandler 345 Airport Road Mattaponi, VA 23110

Certified Mail 7021-0950-0001-4539-2006

RE: Tax Map/GPIN:1623-165X-107 HDID:149-23-035

LOCATION ADDRESS: 345 Airport Road Mattaponi, VA 23110

Dear Gloria Chandler:

This letter is to inform you that the King & Queen County Health Department has evaluated your application for a sewage disposal system/water supply permit or certification letter filed on May 18, 2023.

Unfortunately, we are not able to issue a Construction Permit.

The reason for denial is:

-Insufficient depth of suitable soil to seasonal water table

-Insufficient area of acceptable soil for conventional drainfield

Contact Private Sector to design proposed repair

This decision is based on the information filed with your application. Site and soil evaluations were made in accordance with the *Sewage Handling and Disposal Regulations*, the *Private Well Regulations*, the *Alternative Onsite Sewage System Regulations*, as well as current agency policy.

In accordance with 12 VAC 5-610-230 of the *Sewage Handling and Disposal Regulations* you have the right to appeal this decision. Your written request for appeal must be received within **thirty (30) days** from the date you receive this letter. Please include any facts or other data that would support your appeal. You may also request a refund of the state portion of your application fee if all of the following apply:

- 1) You are the owner of the property AND
- 2) You intend to use it as your principle place of residence AND
- 3) You do not intend to appeal this denial.

Address your request to Richard Williams, MD, Director of Three Rivers Health District at the above address. Refunds are not available under any other conditions. Please include your social security number with your request.

Tax Map/GPIN: 1623-165X-107 HDID: 149-23-035 Page 2 of 2

It is also acceptable to re-apply within 90 days of receipt of this letter without paying a second state fee. After 90 days, a new application fee will be required. When denied for any reason, re-application without a state fee within 90 days may include any change up to and including a new site. Please be certain that the re-application documents are complete and follow all applicable regulations and policies to avoid another denial.

If you have any questions or if this office may be of further service, please let us know.

Sincerely,

Laura

Laura K. Jones Environmental Health Specialist Sr. Three Rivers Health District

CC: D. Mantell- MPPDC

Page 1 of 3

Site and Soil Evaluation Report

Site and Soil Evaluation Report	t HDIN: <u>149-23-035</u>				
General Information					
Date: 06/26/2023	King & Queen County Health Department				
Owner: Gloria Chandler	Phone: 757-790-3208				
Owner Address: 345 Airport Road Mattapor					
Property Address: 345 Airport Road Mattapo					
Tax Map/GPIN #: 1623-165X-107					
	Section: A Block: Lot: 24-26				
Soil Information Summary					
 Position in landscape satisfactory: ■ Yes □ No Slope: 0-1_% Depth to rock/impervious strata: Maxin. □ 					
 Free Water Present: □ Yes ■ No 	Range in inches:				
 4. Free water Present: 4. Free water Present:					
 6. Soil percolation rate estimated: □ Yes ■ No Estimated rate: min/in at inches depth 					
Texture Group: I I II III IV					
•	provide additional data on paraplation test results				
7. Percolation test performed: Ves IN No If yes, provide additional data on percolation test results. Name and title of evaluator: Laura K. Jones, EHSS					
	ibe dispersal area, e.g. absorption trenches) dispersing				
	time of evaluation) to be placed at (inches) depth at				
site designated on permit. Site provides a total of	square feet of absorption area for primary and				
reserve (if applicable).					
site disapproved: Reasons for rejection (check all					
 Position in landscape subject to flooding Insufficient depth of suitable soil over had Insufficient depth of suitable soil to seaso Rates of absorption too slow. Insufficient area of acceptable soil for rec Proposed system too close to well. Other (specify) 	rd rock.				

This form contains personal information subject to disclosure under the Freedom of Information Act. Revised 12/1/2014

Date of Evaluation: 06/26/2023

Profile Description SOIL EVALUATION REPORT

Property ID: 1623-165X-107

Where the local health department conducts the soil evaluation the location of profile holes may be shown on the schematic drawing on the construction permit or the sketch submitted with the application. If soil evaluations are conducted by a private Onsite Soil Evaluator or Professional Engineer, location of profile holes and sketch of the area investigated including all structural features (i.e. sewage disposal systems, wells, etc.) within 200 feet of the site and reserve site shall be shown on the reverse side of this page or prepared on a separate page and attached to this form.

Hole #	Horizon	Depth (Inches)	Description of color, texture, etc.	Texture Group
1	A	0-6	10YR 3/2 Very Fine SL	Ш
	Bt1	6-14	10YR 3/2, 2.5Y 5/3 Matrix w/ few 2.5YR 4/6 Birdseye noticed FSCL grading to SIL at 10"+	-
	Bt2	14-20	2.5Y 6/3 SIL w/ 7.5YR 5/8,5YR 5/8, 10YR 5/1 & 6/2, 2.5YR 4/8 mottles	111
	Bt2	20-28	7.5YR 5/8, 10YR 5/2 matrix CL w/ 2.5YR 3/6 mottles	
	Bt3	28-30	7.5YR 5/8 w/ 10YR 6/2 Clay Loam course/ lite & few 5YR 4/6 Mottles	III
	Bx	30-36	7.5YR 5/8 w/ 10YR 6/2 7 2.5YR 4/8 Clay Loam/ Clay	III-IV
	Bx2	36-44	10YR 6/1 w/ 7.5YR 5/8 & few 2.5YR 4/8 mottles Clay	IV
	Bss	44"+	10YR 6/1 w/ 7.5YR 5/8 & few 2.5YR 4/8 mottles- Slicken Slides noted (Shink/ Swell) Clay	١٧
				-
REMA	RKS: Dep	th to seasonal	water table insufficent for conventional sewage disposal system.	-

This form contains personal information subject to disclosure under the Freedom of Information Act. Revised 12/1/2014

KQ SWAP Application:







